

**Date:** Jan 31, 2024 **Author:** Marley Futerko 604-444-3732 Ext. 337 SN#4504 **Project:** CC  
**The Universal Group:** 9770 199A St Langley, BC V1M 2X7 **Office:** 604-444-3799 **Fig:** 19.2 / 11.15  
**Dwg:** 001

**Comments:**  
 Lexi Development Group Inc  
 Roham Karamiyar 778-772-1312



Township of Esquimalt  
 Job location: 899 Esquimalt Rd & Head St  
 Closure description: Sidewalk & NB Directional Closure  
 Job description: Deliveries and Concrete Boom Pump  
 Tentative date and hours: TBD  
 Traffic Plan based on a 50 km/h speed zone  
 Traffic specifications based on the Traffic Management Manual for Work on Roadways 2020



**Notes:**  
 - Plan was prepared in accordance with MoTI TMM 2020.  
 - Client has been notified of the WorkSafeBC OHS Regulations Part 18 amendment & it is their responsibility to ensure site compliance.  
 - Plan must be reviewed if there are any changes to the findings of risk assessment (provided), or after one year.  
 - Implementation of set up to follow the process outlined in the SJP-019 Device Installation Safe Job Procedure.  
 - Advanced Warning Sign distances may be shortened to suit urban block length.  
 - 3.5m lane width to be maintained.  
 - Driveway access to be maintained.  
 - After working hours, road configuration to be re-instated.



Legend	
	Barricade
	Bollard
	Bus Stop
	C-018-1A
	C-030-6A
	C-202
	C-203-L
	C-203-R
	High Level Wind Device
	R-12
	R-12T
	Tripod Stand
	Work Area